

PEQUEA TOWNSHIP

1028 Millwood Road | Willow Street PA 17584 | P (717) 464-2322 | F (717) 464-4098 | office@pequeatwp.org

Addendum #1 – Dated 02/16/2025

Please find attached a revised Attachment #1 noted on the “Special Provisions to Contract MS-944 (Attachment1-A) Line item work to be completed on or before – dates are corrected.

Please sign, date, and attach this notification and addendum to your current bid packet when turning in your proposal.

Sign

Date

SPECIAL PROVISIONS TO CONTRACT MS-944 (Attachment 1-A)
CONTAINS IMPORTANT INFORMATION FOR THE CONTRACTOR

**The Prime Contractor and subcontractors must comply with all of the following provisions
that are marked with an "X".**

- Traffic Control and Safety Devices to be provided by the Contractor.
(Maintenance and Protection of Traffic to comply with current MUTCD, Publication 212 and Publication 213.)
- Delivery tickets for all materials.
- CS-4171 Certificate of Compliance and/ or TR-465 Daily Bituminous Mixture Certification required for all materials.
- Notify the Municipality Ten working days prior to start of project.
- Work to be completed on or before 8/1/2026. After 8/25/2026 Liquidated damages apply at the rate of \$ 885.00 per calendar day.
- Roadway to be power broomed by (contractor municipality)prior to start of project.
- Excess material to be removed by (contractor municipality)
- Municipality to inspect project.
- Need Bill of Lading for each shipment of bituminous material per Section 702.1(c) of Specifications 408.
Tack Coat required per Section 460, or 409 for superpave, of Specifications 408 and is incidental to paving item unless noted otherwise.
Prime Coat required per Section 461 of Specifications 408.
Bituminous Seal on all abutting pavement and curbs required.
Saw cut or Milled Paving Notch required and incidental to paving item unless noted otherwise.
Scratch/ Leveling Courses to be placed at the discretion of appointed inspector(s).
- Full width pavement with one pass required.
- Municipality reserves the right to limit work completed.
Taper pavement the last 3 feet to curb.
For FOB Source bids, hauling distance will determine selection of bid award.
- Municipality reserves the right to procure material which best suits their requirements after all bids and items are reviewed.
- Incidental Preparation and clean up required. (Project Construction Materials)
- The municipality reserves the right to make an award on the basis of the aggregate total for all like items on which quotations are received.
Provide design, which meets Specifications Form 408 to the municipality 5 days prior to start of work.
- Contractor responsible for defects that occur within one year of applications.
- Contractor required to review proposed project with Municipality's Representative prior to bidding.
- Oil Samples required from each distributor truck by contractor (1) one quart : A.M. & P.M. and witnessed by municipality and retained by municipality. (Oil samples must be placed in an approved type container that is compatible with oil sample.)
- At least three random stone samples to be taken by contractor on project site witnessed by municipality and retained by municipality.
Complete all testing in accordance with Specification Form 408 Section 409 except for superpave volumetric testing.
- Notice to Proceed will be the date of Contract acceptance.
- Final Completion Certificate & Notice of Completion required.
- Future award of Contract will be based on quality of work as determined by the municipality.
- Contractor, notify all residents of pending work to be performed.

My signature signifies that I have read and understand the above special provisions to this contract, and by being authorized by this company to act as their authorized representative, and on their behalf hereby agree to adhere to any and all of the provisions pertaining to this contract.

Contractor's Representative

Date

Company

Municipality's Representative

Date

Pequea Township: 2nd Class

Municipality